REVISED SCALABLE SITE PREPARATION MODEL MARCH 22, 1996

Number of CONNECTIONS Staff

+----+

<u>Equipment</u>	 <u>1-4</u> <u>5-9</u>	<u>10-49</u>	50-99	<u>100-500</u> ¦	Space Requirements AMPS	Electric (B]
Personal Computer	Y	Y	Y	Υ	Y Monitor - H 15.1" W 19.5" D 15.2"	6.2
					Workstation - H 6.3" W 16.5" D 17.6"	
					Keyboard - H 2.5" W 18.5" D 7.5"	
Printer High End	N	Y	Y	Υ	Y H 21.3" W 21.3" D 20.5"	6.0
Low End	Y	Y	Y	Y	Y H 11.7" W 16.6" D 15.9"	3.0
Router/Modem	N	Y	Y	Y	Y 3 sq. ft.	2 _{15.0}
Hub (1 Hub for every 15 users)	N	Y	Y	Y	Y 3 sq. ft.	3 .5
Remote Hub	N	N	N	Y	Y 3 sq. ft.	3 . 5

Number of CONNECTIONS Staff

	++										
<u>Equipment</u>	 <u>1-4</u> <u>5</u>	<u>-9</u>	<u>10-49</u>	<u>50-99</u>	<u>100-500</u> ¦	 Require	<u>eme</u> i	Space <u>nts</u>	<u>AMPS</u>	Electric <u>(B</u> 7	
OA/Mail/Mgmt Server with UPS	N	N		_Y 4	Y	Y	H W D	25.6" 12.4" 18.6"		5 _{10.0}	
								S - sq. ft.			
Dial Up Telephone Line	_Y 6	N		N	N	N		N/A		N/A	
Legacy Server	N	N		N	8 _Y	8 _Y	H W D	25" 9" 20"		5 _{10.0}	

 $\underline{\mathsf{KEY}}$: Y = Yes, required for configuration. N = No, not required for configuration

- 1 = Will operate in a typical office environment with 20-85% relative humidity, within range of 50° to 90° F.
- 2 = Router and Modem will share a dedicated 15 AMP circuit, with a quad receptacle rec
- 3 = Hub requires a one half (.5) AMP per unit, allocated at a rate of approximate server users. The exact requirements will be determined at the site survey.
- 4 = Servers will be placed at Local Social Services' Districts (LSSD) sites within exall LSSD sites may have up to 4 servers, which will be determined at the site sur Agencies typically will not have servers at their sites.
- 5 = Servers/UPS require a dedicated circuit.
- 6 = Local Social Services' Districts and Voluntary Agencies will provide one dial umust order the message business line service from their local telephone company. cost should be included as a site preparation expense. Specific instruct available at the site survey.
- 7 = Isolated grounding of circuits is not required.
- 8 = One legacy server will be required at LSSD sites with 50-99 staff and two legacy required at sites with 100-500 staff.